Date:26/12/2023

To

Mr.Jahirul Hoque Sohel

Kismotpur Korimpur,Chowmuhni.

Noakhali.

Subject: Quotation for Interior Decoration of your Residence / Apartment. @ Chowmuhni.

Dear Sir,

In response to your query regarding the captioned Items, we are pleased to quote below our price offer for the items of your Residence Interior Decoration.

Sl No	Description of items	Sft.	Rate	T Amount
	Ground Floor			
A.	***Drawing***			
1	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,12 mm Mdf Cnc Or Jali Design(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	520	480.00	249,600.00
2	***TV Unit With Display***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Tv Unit With Display Work.Made by 18 mm Burma Teak Board,18 mm Gorjhon Ply,Paneling 3 mm Pvc,12 mm Plain Particale board.1.2 mm Hpl Sheet & Bit.(Super/Mrs/Equivalent).Including Polish Finish,With Hardware With Necessary etc,.As Per Design & Drawing.	96	1,050.00	100,800.00
3	***Book Shelf***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Book Shelf Work.Made by 18 mm Burma Teak Veneer board.18 mm Gorjhon Ply.6 mm Gorjhon Ply,3mm Pvc(Amber/Super/Mrs/Equivalent).6 mm Clear Glass For Palla,Including Lacquer & Docu Finish.Hardware With Necessary etc,.As Per Design & Drawing.	39	1,200.00	46,800.00
4	***Column Paneling***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Beam & Column Paneling Work.Made by 12 mm Burma Teak board.Including Polish Finish With Hardware With Necessary etc,.As Per Design & Drawing.	90	420.00	37,800.00
5	***Folding Door-(Drawing & Dining)***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Folding Door Work.Made by 3"X1.5" Ghamari Wood Or Oak Wood (American Wood) Framing,1"x1" Wooden Molding Bit,6 mm Clear Glass,(Ctg).Including Lacquer Or Docu Finish.Hardware With Necessary etc,.As Per Design & Drawing.	72	1,980.00	142,560.00
B.	***Dining***			

6	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,12 mm Mdf Cnc Or Jali Design(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	295	480.00	141,600.00
7	***Full Height Dinar Wagon***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Dinar Wagon With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,6 mm Mirror Glass For Palla,10 mm Glass Shelf,6 mm Vavel Glass,Including Lacquer/Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	107	1,800.00	192,600.00
C.	***Room-1***			
8	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	140	480.00	67,200.00
9	***Full Height Cloth Cabinet***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Cloth Cabinet With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,6 mm Mirror Glass For Palla,Including Lacquer/Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	72	1,800.00	129,600.00
D.	***Kitchen Area***			
10	***Kitchen Cabinet Uper & Middle Part***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Kitchen Uper & Middle Part Work. Made by 18 mm Gorjhon Ply With .8 mm HPL/Acrylic Sheet Fasting,Back Side Formika Fasting.(Gorjhon Ply,Ahmad,Maya).Structure Framing & Inside 3/4" Gorjhon Ply,6 mm Clear Glass For Palla,10 mm Glass Self,Including Profile Handle,Profile Chanel Azhing,Covja With Necessary etc,.As Per Design & Drawing.	132	2,200.00	290,400.00
11	**Kitchen Cabinet (Lower Part)**	**Sft.**	**Taka**	

	Supplying Making Fitting and Fixing of Kitchen Lower Part Work. Made by 18 mm Gorjhon Ply With .8 mm HPL/Acrylic Sheet Fasting,Back Side Formika Fasting.(Gorjhon Ply,Ahmad,Maya).Structure Framing (3"x1") Gorjhon Wood,Including Profile Handle,Profile Chanel Azhing,Covja With Necessary etc,.As Per Design & Drawing.	82	2,200.00	180,400.00
	1st Floor			
E.	***Open Space***			
1	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,12 mm Mdf Cnc Or Jali Design(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	350	480.00	168,000.00
F.	***M-BED***			
2	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	198	480.00	95,040.00
3	***Full Height Cloth Cabinet***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Cloth Cabinet With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,6 mm Mirror Glass For Palla,Including Lacquer/Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	96	1,800.00	172,800.00
4	***Dressing Unit***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Dressing Unit With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent),6 mm Mirror Glass For Palla,Including Lacquer/Docu Finish,Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	54	1,350.00	72,900.00
5	***TV Unit With Display***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Tv Unit With Display Work.Made by 18 mm Burma Teak Board,18 mm Gorjhon Ply,Paneling 3 mm Pvc,12 mm Plain Particale board.1.2 mm Hpl Sheet & Bit.(Super/Mrs/Equivalent).Including Polish Finish,With Hardware With Necessary etc,.As Per Design & Drawing.	44	1,050.00	46,200.00
G.	***Room - 1***			
6	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	

	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	154	480.00	73,920.00
7	***Full Height Cloth Cabinet***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Cloth Cabinet With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,Including Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	51	1,800.00	91,800.00
8	***Dressing Unit With Study***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Dressing Unit With Study Unit With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent),6 mm Mirror Glass For Palla,Including Lacquer/Docu Finish,Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	46	1,350.00	62,100.00
H.	***Room - 2***			
9	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	135	480.00	64,800.00
10	***Full Height Cloth Cabinet***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Cloth Cabinet With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,Including Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	73	1,800.00	131,400.00
11	***Study Unit***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Study Unit Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent),Including Lacquer/Docu Finish,Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	28	1,350.00	37,800.00
I.	***Room - 3***			
12	***Decorative False Ceiling Work.***	**Sft.**	**Taka**	

	Supplying Making Fitting and Fixing Decorative False Ceiling Work.Made by 2"x1" Gorjhon Wooden Framing.12 mm Plain Particale board,(Partex/Super/Equivalent).Including Docu Finish.Hardware All Complete Work,Making Provisions for Lighting Etc.As Per Design & Drawing.	140	480.00	67,200.00
13	***Full Height Cloth Cabinet***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Full Height Cloth Cabinet With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent).Structure Framing & Inside 3/4" Gorjhon Ply,Back Side 1/4" Gorjhon Ply, With 3 mm Pvc Board,Including Docu Finish.(Palla Both Side And Visual Side Kangaru Docu,Inner Side Normal Docu),Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	36	1,800.00	64,800.00
14	***Dressing Unit With Study***	**Sft.**	**Taka**	
	Supplying Making Fitting and Fixing of Dressing Unit With Study Unit With Dressing Work.Made by 3/4" Gorjhon Board.(Amber/Super/Mrs/Equivalent),6 mm Mirror Glass For Palla,Including Lacquer/Docu Finish,Handle,Lock,Covja,3 Part Drawer Chanel.Including All Necessary etc,.As Per Design & Drawing.	56	1,350.00	75,600.00
J.	***Electric Work***	**RFT/Nos**	**Taka**	
15	1.5 rm Cable Wearing & Netwarking For (Spot Light, T-5 Tube Light/ LED Strip Light) with Labour Cost	2700	18.00	48,600.00
16	LED Srip Light (in mtr)	260	180.00	46,800.00
17	3 Wt LED Spot Light (Drop Ceilling)	130	350.00	45,500.00
K.	**Consultancy, Monitoring & Project Supervision**			
	Consultancy, Monitoring & Project Supervision	L/S	L/S	40,000.00
	Grand Total Amount			**2984620.00**

In Word:Twenty Nine Lac Eighty Four Thousand Six Hundred Twenty Taka Only.

NOTE:

1) Rate will be fixed & Final bill will be Counted after final measurement and it will be checked back along with honourable client.

2) Total sft is not Fixed, Due to Change the Design or any other reason it can be changed.

3) This offer Valid For next 15 days From today. Work Completion Duration Start from the date of Financial Transaction.

Terms and Conditions for payment schedule:

1. 60% payment to be made along with confirmed work order.
2. 20% payment will be paid as 1st running bill after completion of 70% works.
3. 20% payment will be paid as Final bill after completion of 100% works ie: after handover the Apartment.

Duration of Work Completion: Ninety (90) Working Days.

Satisfied customers are our best ambassadors, So we encourage you to give us feedback on how we're doing. We look forward to have more informative dialogue and discussion.

Please call us for any sort of inquires.
Thanks and best regards.

Md. Saifuddin Rasel
Chief Executive Officer
DELIGHT INTERIORS